



## Residential New Building Permit Plan Review Comments

**Application:** PB25-10347

**Date Submitted:** 07/21/2025

**Status:** Issued

**Date Issued:** 08/01/2025

**Address:** 2013 GREY BIRCH PL

**Parcel:** 1478167

**Zoning:** PD

**Subdivision:** WALSH RANCH QUAIL VALLEY

**Lot/Block:** 13/61

**Description of Work:** New Single Family Residence w/3rd Party Review and Inspections

**ADA TDLR:**

**Energy Code Compliant:**

**Applicant:** Adriana Perez

**Owner:** CITY OF FORT WORTH

100 E 15th St 100

100 FORT WORTH TRL

Fort Worth, TX 76102

FORT WORTH, TX 76102-6312

9722446925

### Building Classification:

Occ Class	Const Type	Square Feet	Occ Load	Use Description
R-3	VB	2740		Living Space
U	VB	502		Utilities

### Sprinkler Sys Req:

**Comment:** Signs, Retaining Walls over 4', Fences, Dumpster Enclosures over 6', and Parkway Approaches and Sidewalks require separate permits and reviews.

### Required Corrections:

Planning Development Department



## Residential New Building Permit Plan Review Comments

### ***Building***

**Reviewer: Adriana Perez**

**Email: Adriana.A.Perez@BureauVeritas.com**

**Phone: 682-227-7436**

1. Bureau Veritas Zoning Notes: Walsh Ranch

Zoning PD522 to R-1 Exhibit E included with all plan submittals. Address: 2013 Grey Birch Pl

Lot coverage 31.31% A-5: 60% max A-7.5: 50% max

Height 29'-3 1/2"

Lot width at build line over 30': Yes No

Verified driveway does not exceed more than 50% of front yard: Yes No

(Measured from front wall of house to front property line)

Exhibit E: Removes projected front yard setback requirements in Section 6.101(A)(D).

Front yard setback of 15 feet (or standard zoning setback if less) applies to residences with rear alley access for lots up to 7,800 sq ft.

Provided front yard setback: 15'-0 3/4" w porch encroachment

Provided side yard setback: L 14'-2" R7'-1" Provided rear yard setback: 19'-9"

Number of bedrooms: 4

Parking spaces (9' x18') provided: 2 in Garage, 2 Driveway  
(Requirements: 3 bdrms=2; 4 bdrms=3; 5 bdrms= 4; 6 bdrms=5)

Masonry Requirements: Over 50% on all sides?

(Masonry is considered brick, stone, cementitious fiber concrete products or stucco)

Trees shown on plot plan: 2

Fences cannot encroach in front of a 20' build line if the corner lot has a projected 20' build line.

### **Approval Table:**

Task Name	Task Status	Completed Date	Task Rev Name
Application Submittal	Routed for Electronic Review	07/22/2025	Latrica Jelks
Water Development Review	Approved	07/24/2025	Elizabeth Armendariz
Transportation Impact Review	Approved	07/24/2025	Lamonica Smith
Urban Forestry Review	Approved	07/30/2025	Scott Edwardson
Zoning Review	Approved	07/30/2025	Scott Edwardson
PARD Review	Not Required	07/23/2025	Germaine Joseph
Building Plan Review	Approved	07/30/2025	3PTY BUREAU VERITAS
Issue Permit	Issued	08/01/2025	Patricia Martinez

Planning Development Department

---

The City of Fort Worth \* 100 Fort Worth Trail \* Fort Worth, TX, 76102  
817-392-2222 \* Fax 817-392-8105



## Residential New Building Permit Plan Review Comments

Inspections			
Mechanical Plan Review	Approved	07/30/2025	3PTY BUREAU VERITAS
Plumbing Plan Review	Approved	07/30/2025	3PTY BUREAU VERITAS
Electrical Plan Review	Approved	07/30/2025	3PTY BUREAU VERITAS
Plans Coordination	Approved	07/30/2025	Scott Edwardson

### General Comments and Additional Permit Information:

**Reviewer: Scott Edwardson**  
**Email: Scott.Edwardson@fortworthtexas.gov**  
**Phone: (817) 392-6288**

1 Zoning Plans Exam  
Residential Zoning Review Notes PB25-10347 – 2013 Grey Birch Pl.  
Planning and Development Department PLAN #: N-6376 A Rear  
Zoning Review Notes: All reviews are pending stakeout inspection  
CFW Zoning Ordinance # 13896-22519

Permit data confirmed on: 07/30/2025

By: Scott Edwardson [817-392-6288]

Scope of project: New SFR

HOLD NOTES: All items labeled "HOLD" must be addressed

SUMMARY: Permit meets minimum standards Y  
Holds: \_\_\_\_\_

Zoning district: "PD522 to R1" Type of layout: One-Family Detached

Official Plat: Attached to plans lot/block number verified Y (Walsh Ranch Quail Valley Blk 61 Lt 13)  
FP-22-128 Filed/Applied 08/03/2023

Building Square footage: R-3: 2748 U: 502  
Slab SF: 1887  
Lot SF: 6026  
Lot coverage: No % maximum, including all structures (Provided 56.96%)

Height: 35' maximum (provided 29.29' )

Lot Width: 30' minimum at building line (Provided 50.23' )

Front yard driveway coverage: % maximum (Provided 0% - Rear)

Planning Development Department



## Residential New Building Permit Plan Review Comments

Setback restrictions: (The front yard setback in residential districts shall be the greatest of: The platted building line; The setback for the applicable zoning district; or the setback of the nearest building on either side that is the closest to the street, up to a maximum setback of 50 feet, provided that said setback is not the result of a variance granted by the Board of Adjustment)

Front: 0' minimum per plat (Provided 20.00')

Houses on either side: \_20.00'\_ / \_20.00'\_ per 3rd party site plan (verify on aerial photo)

Sides: 3' one side and 5' minimum (Provided 14.17' & 7.08')

Rear: 5' minimum (Provided 19.75' )

Note: As applicable, any fence located within an easement will require permission of the easement holder(s) to encroach.

Parking spaces:

Ord. 21528 Single Family Home: Two spaces located behind the front building wall for dwelling units with three or fewer bedrooms, plus one space located behind the front building wall or in the driveway for each bedroom above three.

# Bedrooms: 4 Parking spaces required 3 provided 4

Required parking spaces must be hard surface and dust free (asphalt or concrete). All maneuvering space must be located off of the public right of way.

Urban Forestry: property is vested, infill, or has approved UFC permit: (Vested FP-22-128) provided Y

An infill house shall be required to have a minimum 3" caliper front yard tree of choice, and one minimum 3" caliper street parkway tree as approved by the City Forester.

Single Family Design Standards:

The same elevation shall not be permitted within a six lot pattern, on an adjacent lot or on a lot directly across the street.

No attached garage facing a public or private street may project greater than eight (8) feet in front of the front wall of the house in all Single-Family Districts.

Additional Comments:

Sec. 22-176. Curb cuts and laid-down curb permit procedures.

The location of ingress and egress driveways shall be subject to approval of the city traffic engineer under curb cut or laid-down curb permit procedures. Driveways shall not exceed sixty-five (65) per cent of the property frontage. There shall be a minimum of twenty (20) feet of curb along the street between driveways where there is more than one driveway on property under unified ownership or control and used as one premise. The decision of the city traffic engineer may be appealed to the city council. (Code 1964, § 26-102.3; Ord. No. 8288, § 1, 3-10-81)

Planning Development Department

---

The City of Fort Worth \* 100 Fort Worth Trail \* Fort Worth, TX, 76102  
817-392-2222 \* Fax 817-392-8105

**SINGLE FAMILY HOME: DWELLING UNIT:** A building, or any portion thereof, containing a complete set of independent living facilities for occupancy and use by one family, including permanent provisions for living, sleeping, eating, sanitation, and cooking within a kitchen for the exclusive use of the occupants whose intent is to habitat the dwelling unit.

**COOKING EQUIPMENT:** A stove, range or other such appliances, which requires a 220V or gas connection that is used, designed, or intended to be used for the cook and preparing of food.

A sidewalk is required for all frontages facing a street  
<http://fortworthtexas.gov/planninganddevelopment/permits/streets/>

**Reviewer:** Elizabeth Armendariz  
**Email:** WaterApps@FortWorthTexas.gov  
**Phone:** 817-392-8250

## 2 WATER APPLICATIONS

\*\*\* IMPORTANT\*\*\* PLEASE READ WATER AND SEWER SERVICE LOCATION REQUIREMENTS \*\*\*

---

Sec 5.18.2.1 Meter boxes can only be installed in non-paved areas. Water service and meter box must be installed 1-foot offset from the property line in the parkway and have a 9-foot horizontal separation from the sewer service. The normal location for meter boxes is 2.5 feet behind the back of curb.

In no case shall the water meter box (and meter) be outside of the public right-of-way or water easement.

Sec 6.4.1.3 Wastewater service should avoid placement in driveways and have a 9-foot horizontal separation from the water service.

Service should be installed South or West of the proposed driveway location.

To prevent delays for a meter set, ensure the following criteria is met:

- Address must be clearly posted, i.e., visible and big enough to see
- No debris or material over the meter box

**Reviewer:** Lamonica Smith  
**Email:** Lamonica.Smith@fortworthtexas.gov  
**Phone:**

## 3 \*\*\*\*Transportation Impact Fees\*\*\*\*

2025 rate with no adequate facilities discount.